



Desilting, Rehabilitation and Landscaping of the Line Drainage Canal and Centerline in Baywalk, Plugging of Illegal Pipes along the Seawall, Wiring Installation from Padre Faura to San Antonio Abad of the Submersible Pumps of the Wastewater Interceptor, Desilting of Intake Drainage Canals along Roxas Boulevard, and Construction of Vertical Gardens with Benches on the 3 Outfalls along the Baywalk

BID BULLETIN NO. 1

May 26, 2021

All prospective bidders are hereby informed of the following amendment/s and/or clarifications for the above stated project;

SPECIFICATIONS

A. Desilting, Rehabilitation and Landscaping of the Line Drainage Canal and Centerline in Baywalk	
A.1	Desilting of Existing Lined Canal Including Hauling and Disposal of Spoils
A.2	Reinforcing Steel Bars (Grade 40) (Minor Structures)
A.3	Structural Concrete Class "A" (Minor Structures)
A.4	Fabrication/Installation of Steel Grating Cover and Steel Casing
A.5	Green Fence Wire Mesh (3 x 2m)
A.6	Laying of Vigan Tiles
A.7	Concrete Stairs with Stainless Steel Railings
A.8	Plastering of Seawall (Class "B", 50 mm thk)
A.9	Landscaping
B. Plugging of Illegal Pipes along the Seawall	
B.1	Concreting Works
B.2	Sandbagging
C. Wiring Installation from Padre Faura to San Antonio Abad	
C.1	Wiring Installation of Submersible Pumps
C.2	Installation of Submersible Pumps
C.3	Installation of Water Line
D. Desilting of Intake Drainage Canals along Roxas Boulevard	
D.1	Cleaning Culvert in place (910mm dia.) Half Silted
E. Construction of Vertical Gardens with Benches on the 3 Outfalls along the Baywalk	
E.1	Bike Racks with Vertical Garden
F. Temporary Facilities/ Miscellaneous Works	
F.1	Construction of Field Office/Bodega
F.2	Billboard/Signages
F.3	Construction Safety and Health
Spl	Mobilization/Demobilization

BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
A. Desilting, Rehabilitation and Landscaping of the Line Drainage Canal and Centerline in Baywalk					
A.1	Desilting of Existing Lined Canal Including Hauling and Disposal of Spoils	1,113.00	l.m.		
A.2	Reinforcing Steel Bars (Grade 40) (Minor Structures)	8,852.74	kgs		
A.3	Structural Concrete Class "A" (Minor Structures)	65.59	cu.m		
A.4	Fabrication/Installation of Steel Grating Cover and Steel Casing	318.00	sets		
A.5	Green Fence Wire Mesh (3 x 2m)	100.00	units		
A.6	Laying of Vigan Tiles	2,314.00	sq.m.		
A.7	Concrete Stairs with Stainless Steel Railings	20.00	sets		
A.8	Plastering of Seawall (Class "B", 50 mm thk)	443.00	sq.m.		
A.9	Landscaping	12,750.00	sq.m.		
B. Plugging of Illegal Pipes along the Seawall					
B.1	Concreting Works	30.00	sets		
B.2	Sandbagging	7,500.00	bags		
C. Wiring Installation from Padre Faura to San Antonio Abad					
C.1	Wiring Installation of Submersible Pumps	1.00	job		
C.2	Installation of Submersible Pumps	1.00	job		
C.3	Installation of Water Line	1,500.00	l.m.		
D. Desilting of Intake Drainage Canals along Roxas Boulevard					
D.1	Cleaning Culvert in place (910mm dia.) Half Silted	9,373.00	l.m.		
E. Construction of Vertical Gardens with Benches on the 3 Outfalls along the Baywalk					
E.1	Bike Racks with Vertical Garden	1.00	job		
F. Temporary Facilities/ Miscellaneous Works					
F.1	Construction of Field Office/Bodega	40.00	sq.m.		
F.2	Billboard/Signages	2.00	sets		
F.3	Construction Safety and Health	1.00	l.s.		
Spl	Mobilization/Demobilization				

This Bid Bulletin shall form an integral part of the bid documents for the project.


USEC FRISCO SAN JUAN JR.
 BAC Chairman